



HENEGHAN AND ASSOCIATES, P.C.

CIVIL ENGINEERS • LAND SURVEYORS

WWW.HAENGR.COM

Since 1986

Addendum No. 3

City of Litchfield Project Wesley – Water Main Extension West of I-55

H&A File No. 02134-401

September 18, 2018

The Contract Documents prepared by Heneghan & Associates, P.C. for the Project Wesley - Water Main Extension West of I-55 for the City of Litchfield, dated August 2018, are hereby amended or clarified as follows:

PROJECT SPECIFICATIONS

Changes/additions/clarifications to the project specifications are as listed below:

Technical Provisions:

Section 41.04: Where crossing the existing paved access road along Route 16, the backfill shall be made with excavated material except that the final 12-inches of backfill shall be made with **SELECT GRANULAR BACKFILL**. Additionally, settlement of the trench at the locations here the water main crosses the paved access road shall be made with **SELECT GRANULAR BACKFILL**. This work shall be incidental to the unit price of the water main installation.

Section 41.18 shall read as follows: Where called for on the Drawings, the water main shall be installed in PVC casing of the size shown on the Construction Drawings. PVC casing shall be C905, DR 21, or equal. The limits of the PVC casing areas shall be staked by the OWNER. As there are currently no known structures or other limiting factors in these areas, the PVC casing may be installed in an open trench. Backfill for Open-Cut PVC Casing Pipe shall be as specified in Section 41.04 and will be incidental to the unit price of the PVC casing pipe installation and no additional compensation will be allowed. Measurement in lineal feet shall be made along the centerline of the PVC casing as installed. Backfill shall be assumed to be under rigid surfaces as the Open-Cut PVC Casing is being installed under a proposed concrete driveway entrance. Therefore, backfill shall be with **SELECT GRANULAR BACKFILL (CA-6 or equal)** except that the top 6"-12" shall be backfilled with acceptable excavated material.

End of Addendum.

Ronald M. Paul, P.E.
Project Manager
Heneghan & Associates, P.C.

□ 838 East McCord
Centralia, IL 62801
(P) 618-533-6525
(F) 618-533-6652

□ 310A Vision Drive
Columbia, IL 62236
(P) 618-281-8133
(F) 618-281-8290

□ 5213D Mae Drive
Godfrey, IL 62035
(P) 618-466-8076
(F) 618-466-8078

□ 1004 State Highway 16
Jerseyville, IL 62052
(P) 618-498-6418
(F) 618-498-6410